

SPECIFICATIONS
FOR
ELM/PRINCE ALLEY SEWER REPAIR
City of Negaunee, Michigan

Prepared by:

City of Negaunee

Department of Public Works
March 9, 2022

QUOTE REQUEST

CITY OF NEGAUNEE

Quotes are requested for the: Construction of **ELM/PRINCE ALLEY SEWER REPAIR**, City of Negaunee, Marquette County, Michigan. The project includes 244 feet of sanitary sewer replacement on Elm/Prince Street Alley in the City of Negaunee, Michigan. The work includes HMA surface removal, bypass pumping, dewatering, removing sanitary sewer and manholes, placing new sewer and new manholes, placing trench backfill, placing gravel, and traffic control.

Quotes can be emailed directly to the City of Negaunee and addressed to: mdaavettila@cityofnegaunee.com and clerk@cityofnegaunee.com. Quotes can also be mailed or dropped off to the City of Negaunee and addressed to: **Negaunee City Clerk, City of Negaunee, P.O. Box 70, 319 W. Case Street, Negaunee, MI 49866**, until 10:00 a.m. ET, March 14, 2022, at which time these quotes will be evaluated and a contractor recommended.

Direct any questions to Mark Daavettila at the City of Negaunee offices.

The Owner reserves the right to waive any informalities or to reject any or all quotes.

City of Negaunee

Elm/Prince Alley Sewer Repair

This project includes sanitary sewer replacement in City of Negaunee. The project will include 140 feet of 8 inch PVC with a new manhole on the west end of the Elm St alley. The project will also include 125 feet of 8 inch PVC heading north with a new manhole on the north end of the Elm St alley. The sewer depth is approximately 6.5 feet-8 feet deep.

Description of Work

Only the bid line items will be paid. Only the 15' wide alley can be disturbed, no driveways shall be disturbed during construction.

Mobilization shall be in accordance with MDOT Specifications.

Pavt, Rem shall include removing existing HMA and materials to a depth of 9 inches. No extra compensation will be paid for frost/frozen ground issues.

Bypass Pumping and Dewatering shall include all labor, equipment, materials, including 6A stone necessary to maintain sanitary flow and groundwater during the sewer replacement work.

Sanitary Sewer, 8 inch, PVC shall include all trench excavation and backfill compacted in 12" lifts to 95 percent, SDR 26 pipe, elastomeric gasket push-on joints.

Sanitary Sewer Manhole & Cover, 48 inch shall be in accordance with MDOT section 403. Castings shall be MDOT Cover Type Q.

Sanitary Sewer Lateral Connection shall include all labor, equipment, fittings, and materials to connect sanitary sewer laterals back to the newly installed sanitary sewer main.

Aggregate Base, 8 inch shall be MDOT 22A gravel and graded and compacted to 98 percent.

Traffic Control shall include all devices, signs, cones, and flaggers necessary to provide traffic control.

Schedule:

Award Contractor: March 14, 2022

MISDIG Clear: March 17, 2022

Contractor Starts: March 17, 2022

Contractor Complete: April 11, 2022

The successful bidder will provide the City of Negaunee with proof of public liability (\$500,000 minimum) and property damage (\$500,000 minimum) insurance to protect the City of Negaunee and any property owners against any and all claims arising out of the performance of the contracted services.



Description	Units	Qty	Unit Price	Total
Mobilization, Max. 10%	LSUM	1		
Pavt, Rem	Syd	585		
Bypass Pumping	LSUM	1		
Dewatering	LSUM	1		
Sanitary Sewer, 8 inch, PVC	Feet	265		
Sanitary Sewer Lateral Connection	Each	9		
Sanitary Sewer Manhole & Cover, 48 inch	Each	2		
Aggregate Base, 8 inch	Syd	585		
Traffic Control	LSUM	1		

TOTAL BID

\$

(words)