

**City of Negaunee
PO Box 70
319 W. Case Street
Negaunee, MI 49866
906 475-9991**

INVITATION FOR BIDS

Sealed bids will be received by the City of Negaunee located at 319 W. Case Street, Negaunee, Michigan, 49866 until 1:00PM, April 24, 2023, for **Custom Movable Platform System** for the Negaunee Downtown Enhancement Project.

Bid shall be submitted and addressed to the Negaunee City Clerk, City of Negaunee, PO Box 70, 319 W. Case Street, Negaunee, MI 49866. Envelope shall be sealed and clearly marked "**Bid for Custom Movable Platform System**"– Negaunee Downtown Enhancement Project." Bids must be received before or by the above date and time. No fax or email bids will be accepted.

Bids will be opened on April 24, 2023, at 1:00PM at **319 W. Case Street (City Hall), second floor conference room.**

The City reserves the right to accept any or all bids or accept any part of a bid. Each of the items may be purchased individually or as a lump sum bid.

BID FORM

Vendor: _____

Address: _____

City of Negaunee – Streetlight Vendor				
Item Description	Quantity	Unit	Unit Price	Total Price
Item 1		Each		
Item 2 (total shipping)		Each		

TOTAL BID

\$

Item 1: Custom Movable Parklet Platform Modular System (Streetlife or Equivalent)

Quantity: 12

Movable platforms that can be connected together either end to end or side to side.

Material: Decking material to be 3/16" Coreten weathering steel, with panel size to be 2' x 6', and bolted to base frame with eight countersunk stainless steel bolts. All edges and corners to be ground so no sharp edges are exposed.

6" framework can be one piece (hot dip galvanized) or assembled pieces bolted together with galvanized bolts.

Approximate size per parklet to be 6' wide x 8' long so that when placed in groups of three they measure 8' X 18" and once assembled can be moved via forklift pockets in the 8' sides of the units.

The overall height of the parklet panels to be 6" or curb height.

There will be eight leveling bolts with pads that will extend from zero to 2" to make up elevation differences at the locations where they will be placed. The leveling bolts will be accessed from the top side of the parklet prior to the floor plates being placed onto the frame from the top.

The parklet base frames will be hot-dip galvanized including the adjusters.

Bolt on railing to be 36" high x 8' long on either of the 8' sides to meet MIBOCA codes for loading and strength (200 lbs at any location perpendicular to the top rail or 50 lbs per foot the entire rail). Railings to be hot dip galvanized posts with hot dip galvanized top rail and stainless cable rails between the posts and top rail, OR other design to be proposed by fabricator and approved by owner.

On any entrance/exit location, a 12" wide ramp of 3/16" hot dip galvanized checkerplate is to be provided and hinged to the upper edge of the platform. Hinge type and location by fabricator and approved by owner.

Eight planters comprised of weathering steel shall be manufactured to be installed on the assembled ends of the connected platforms. Size shall be 5' long and 24" deep. Solid base with bottom holes for drainage.

Item 2: Shipping (priced by shipping source)

Shipping by source

Delivered to:600 Cherry Street, Negaunee, Michigan 49866